

## Bill of Quantities

**Name of Work :- Preventing the waste water flowing to ground level tank from the washing area in the Administrative Block at Kozhikode KSRTC Bus Terminal Complex**


Technical Sanction of the work : Estimated PAC- Rs. 1,10,000


### TENDER SCHEDULE

Sl No	Description of work	Unit	Quantity	Rate	Amount
1	Dismantling precast concrete block of stone slabs removing carefully and stacking the serviceable materials for reuse in floors etc. Including stacking within 50m lead	m <sup>2</sup>	20 m <sup>2</sup>		
2	Earth work excavation in hard soil and depositing on bank with all leads upto 50m and lift upto 150m including breaking clods watering, ramming, consolidating and labour charges etc complete.	m <sup>3</sup>	1.5m <sup>3</sup>		
3	Providing and fixing 100mm G.I.Pipes complete with G.I.fittings including trenching and refilling etc and cost conveyance of all materials and labour charges etc complete.	m	5m		
4	Providing and laying departmental 80mm thick factory made cement concrete interlocking paverblock of M-30 grade made by block making machine with strong vibratory compaction, of approved size , design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with	m <sup>2</sup>	82m <sup>2</sup>		

	line sand etc. All complete as per the direction of Engineer in charge, ( 70% of dismantled stone)				
5	Providing and laying 80mm thick factory made cement concrete interlocking paverblock of M-30 gradw made by block making machine with strong vibratory compaction of approved size, design and shape laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand filling the joints with line sand etc. All complete as per the direction of Engineer in charge. ( 30% of dismantled stone)	u <sup>2</sup>	10M <sup>2</sup>		
6	Supplying and spreading quarry waist/mooram for levelling the sinking portion including cost conveyance of all materials and labour charges etc.	m3 ✓	5m3 ✓		
7	Cement concrete 1:1.5:3 using 20mm size hard granite broken stone for bottom slab of tanks includind all form work, watering, curing, cost and conveyance of all materials and labour charges etc upto plinth level. Complete but excluding reinforcement.	m3 ✓	4.6m3 ✓		
8	Coring the concrete walls for providing pipes including cost conveyance of all materials and labour charges.	nos ✓	2 nos ✓		
9	Steel reinforcement for R.C.C work including straightening, cutting, bending , placing in position and binding all	Kg ✓	230 ✓		

complete above plinth level Thermo Mechanically Treated Bars.				
---	--	--	--	--

  
 Principal Project Consultant  
 KTDFC

	<b>Kerala Transport Development Finance Corporation Ltd</b> Trans Towers (6 <sup>th</sup> Floor), Vazhuthacaud, Thiruvananthapuram, Telephone: 0471-2327881, 2326883, web: www.ktdfc.com			
	<b><u>Tender Notice</u></b> <b><u>Tender No.27/KTDFC/BOTP/KKD/2018</u></b>			
<b>Name of Work</b>	<b>Period of completion</b>	<b>EMD</b>	<b>Cost of Tender form</b>	<b>Estimated PAC</b>
Preventing the waste water flowing to ground level tank from the washing area in the Administrative Block at Kozhikode KSRTC Bus Terminal Complex	one month	Rs.2750 ✓	Rs.500 plus 18% GST = Rs. 590 ✓	Rs. 1,10,000 ✓

Sealed Competitive Tenders are invited for the work of **Preventing the waste water flowing to ground level tank from the washing area in the Administrative Block** at Kozhikode KSRTC Bus Terminal Complex. Tender forms will be available at the KTDFC website **www.ktdfc.com** from **20.06.2018**. Last date of receipt of tender will be **29.06.2018** at 11am. Tender will be opened on **29.06.2018** at 11.30 am.

For more details please visit **www.ktdfc.com**

For any further details, please contact KTDFC (Ph: 0471 2327881).

Date: 19..06.2018

  
 Principal Project Consultant

12